

PLUMBING PERMIT * E12-14356
 Job Address: 6100 CARILLON PT , 1-2 NONE

APPLICANT
 Mike Timmons (206) 762-1960
 430 SW 153rd St
 Burien, WA 98166



FINALED 5-17-12

MyBuildingPermit.com

Work Type: ALTERATION
 Use Type: COMMERCIAL

Proj./Tenant: CARILLON PROPERTIES W
 Related Prmt #: BLVD/PLM

Area of Work:
 Fair Market Value: \$6,200.00

CONTRACTOR
 ENVIROMECH
 (206) 762-1960

OWNER
 * CARILLON PROPERTIES W BLVD

Job Notes:
 (1 Primary Building, 1 Installation of fixtures, 3 Dishwasher, 3 Hot Water Heater, 3 Sink, 9 Total Number of Fixtures) in 3 break rooms on 1st and 2nd floor.

TOTAL FEES: \$ 81.36
 COUNT OF FEES: 2

PLUMBING FIXTURES

Bathroom Sink:	Floor Drain:	Backflow Preventer (in.):
Bathtub:	Hose Bib:	Water Service (in.):
Bidet:	Elec Water Heater: 3	Shower:
Clothes Washer:	Ice Maker:	Sink: 3
Dish Washer: 3	Laundry Tub:	Toilet:
Drinking Fountain:	Pressure Reducing Valve:	Urinal:

Plumbing Permit Conditions:

- Do not cover any work until an inspection has been approved.
- New or replaced water service piping materials must consider the buildings electrical grounding system. At a minimum, 10 feet of metallic piping must be in contact with earth when the piping is part of the electrical ground system (or a licensed electrician shall install approved electrical ground rods).
- Hot Water Heaters - please see "Tip Sheet #7 - Water Heaters for Installation tips.
- New Drain, Waste and Vent systems must be tested with a minimum of 5 psi of air or by filling the system with water to provide not less than a 10-foot head on all piping. Test must be applied for 15 minutes and witnessed by inspector.
- New or replaced water supply lines must be tested and proved tight under a water pressure not less than the working pressure under which it is to be used.

	Date	Inspector
Water Service		
Groundwork		
Rough In/ Test	4/17/2012	PXA
Backflow Inspection		
Final Inspection	5/17/2012	PXA

Notes: * 4/25/2012 R/I TEST II PXA

